


**DEMOLITION NOTES:**  
 A. Remove existing wood door, hardware, HM frame and wire glass complete.  
 B. Existing surface mounted light fixture to be removed by owner. Circuits and switching to be reused for new lights.  
 C. Remove sliding glass panels and wood trim.  
 D. Remove existing 12x12 vinyl tile floor and 4" cove base in entire room.  
 E. Remove existing rubber stair treads and risers and 4" cove base complete on all stairs and landing from first floor to lower level.  
 F. Remove existing metal threshold .  
 G. Existing floor register to remain.  
 H. Remove existing 12x12 vinyl tile on landing.  
 J. Remove vinyl reducer strip at carpet edge.

**ADDENDUM NO. ONE**

 WAKELY ASSOCIATES, INC./ ARCHITECTS 30500 Van Dyke Avenue, Suite M-7, Warren, Michigan 48093 PH: 586.573.4100 FX: 586.573.0822 www.wakelyaia.com	Fraser Public Schools Administration Building Lobby Renovation		DRAWN BY: BJS	PROJECT NO.: 201865
	SCALE: 1/4" = 1'-0"		APPROVED BY: BJS	REFERENCE SHEET: XXX
			DATE: 03-03-2020	SHEET NO.: A-1.1