


- NEW WORK NOTES:**
1. New LVT floor tile and new 4" vinyl cove base in entire room.
 2. New 3-0x7-0 flush wood solid core door (stain) in new HM frame (paint) with 1/4" laminated glass sidelite. Verify frame opening in field prior to ordering new frame. Hardware to be: closer, hinges, Classroom Lockset with lever handle, wall stop and kick plate.
 3. New vinyl reducer strip at LVT/carpet edge.
 4. Apply new 3/8" gypsum board over all wall surfaces full ht. then Paint all walls in room full ht.
 5. Paint existing 12x12 acoustic tile ceiling.
 6. Fill in hole in ceiling tile prior to painting.
 7. Owner to provide & install New 1x4 surface mounted, 2 lamp, LED light fixture, connect to existing circuits and switching.
 8. Existing supply air diffuser to remain. (Clean and Paint)
 9. New acrylic signage surface mounted to exterior wall. (By owner)
 10. Paint existing frames and walls full ht to match adjacent color. Verify color with owner.
 11. New Rubber 4" vinyl cove base, stair treads, risers, nosings and landing surface on all existing stairs from first floor to lower level.
 12. New 3-0x7-0 flush wood solid core door (stain) in new HM frame (paint) with SG4 security glass in sidelite. Verify frame opening in field prior to ordering new frame. Hardware to be: closer, hinges, Classroom Lockset with lever handle, wall stop and kick plate.
 13. New SG4 security glass with 2"x14" slot on bottom and 1/2" dia. voice holes in 8" dia. circular pattern in new HM window frame (paint). Frame size to be +/- 34"Wx33"H (V.I.F.) See Detail No.1/A-1.4
 14. Cut new base to stop/start each side of existing plastic corner guard for new base work.
 15. Cut new flooring around existing floor register.
 16. Owner to Extend existing light switch boxes and receptacle boxes as required to be flush with new wall surface. Verify quantities and sizes in room.
 17. Existing wall mounted security camera to be removed and reinstalled by Owner.
 18. Owner to install New Police Emergency button on wall. Connect to existing District security system.
 19. Patch walls after frame removal and paint to match existing colors.
 20. Provide new wood casing on both side and all around new HM frame. Stain to match new doors.

ADDENDUM NO. ONE

 <p>WAKELY ASSOCIATES, INC./ ARCHITECTS 30500 Van Dyke Avenue, Suite M-7, Warren, Michigan 48093 PH: 586.573.4100 FX: 586.573.0822 www.wakelyaia.com</p>	Fraser Public Schools Administration Building Lobby Renovation	DRAWN BY: BJS	PROJECT NO.: 201865
		APPROVED BY: BJS	REFERENCE SHEET: XXX
		DATE: 03-03-2020	SHEET NO.: A-1.2
		SCALE: 1/4" = 1'-0"	